

PAKISTAN TELECOMMUNICATION COMPANY LIMITED
HEADQUARTERS G-8/4 ISLAMABAD

SUBJECT: - **RENOVATION WORK OF ICT HOSTEL AT CDDT BUILDING H-9/1 ISLAMABAD.**

The following terms and conditions are strictly required to be fulfilled by the Building Contractor(s) for participation in competition/execution of works specified in above captioned Tender, floated by the PTCL H/Q Islamabad.

All contractors will enclose C.D.R in shape of bank draft/pay @ 5 % of tender cost. The call deposits will be released to un-successful bidders after the checking / scrutiny as per PTCL rules.

The CDR amount shall be remained valid and operative (60) days beyond the expiry of Twelve (12) months.

The CDR being unconditional and irrevocable undertaking to PTCL shall be independently confirmed by the bank before its discharge/encashment, especially before its expiry.

The proceeds of the CDR is payable to PTCL as compensation for any loss resulting from the Contractor's failure to complete any of its obligations under this Contract.

Submission method of bids and deadline

- a) Bidders shall make two separate submissions in two sealed envelopes. One sealed envelope will contain the Technical Offer (un-priced bid) along with specifications and all other technical details ensuring that the envelope must be marked as "Technical Offer".

A second sealed envelope will contain the commercial offer (priced bid) with the cost breakdown as per PTCL price schedule / BOQ, ensuring that this envelope must be marked as "Commercial Offer".

- b) Both above sealed envelopes must bear PTCL Tender / RFQ reference number ONLY without any other details or name of bidder or any other reference etc.
 - c) Both above bids must be deposited in the office of Manager (Maintenance) PTCL HQs, G-8/4, Islamabad on or before the closing date and time as advised by PTCL in Invitation to Tender letter.
 - d) Any bid received by PTCL after the deadline for submission of bids prescribed by PTCL will be rejected and /or returned un-opened to the bidder.
1. All material and equipment shall be arranged by the contractor for the execution and faithful completion of the work.
 2. The firm / contractor are prohibited to publishing things in the press relating to the contract.
 3. PTCL shall not make any payment(s) to the contractor without acceptance of the completion reports supplied by the contractor, to the effect that the Civil work(s) has been completed to the entire satisfaction of the PTCL and the same is inspected and duly verified by the End user and Rates Validity for one year.
 4. The contractor shall provide certificate of satisfactory services duly verified by the Engineer building.
 5. The type of work(s) for which rates are tendered shall be mentioned on top of the Tender document by the contractor in clear handwriting or typed in block letters, otherwise the same will be considered invalid by PTCL.
 6. The Tender Committee reserves absolute and final right to accept or reject any tender or all Tenders without assigning any reason in respect thereof.
 7. The contractor will be bound to comply with the work order delivered after approval of Tender. A penalty of 0.5% of the contract value per day will be imposed if the contractor fails to take work in hand within 7 days after

issuance of receipt of work order. The same penalty is also applicable for delayed performance of work beyond the specified period.

8. The contractor will not claim any compensation or damage during execution of work for any reason whatsoever.
9. The contractor shall under no circumstances sublet or assign the work or the contract without the prior written approval of PTCL; otherwise its security shall stand forfeited by PTCL.
10. The contractor shall strictly comply with all the terms and conditions contained herein or in the Tender documents. In case of dispute between contractor and any supervisory officer(s) of PTCL, the decision of the PTCL will be final. In the event that the contractor violates/commits breach of any terms and conditions of this contract the PTCL H/Q Islamabad credit to the PTCL accounts, this decision will stand unchallenged in any court of law.
11. Contractor shall sign each page and shall submit his acceptance of the above terms and conditions on Judicial/ Legal Stamp Paper duly attested by the Notary Public/Oath Commissioner at the time of execution of work.
12. Contractor shall be liable to comply with all applicable labour laws.
13. In case of any query/inquiry, feel free to contact Manager (Maintenance) on telephone number 051-2250127.
14. **TERMINATION:** If the vendor fails to comply with any of the conditions mentioned herein or the Contract/ Purchase Order, the Contract/ Purchase Order may be terminated immediately by PTCL through a notice in writing and any costs incidental thereto shall be borne by the vendor. Such termination shall not prejudice any legal action subsequently taken by PTCL against the vendor for breach of contract / Purchase Order.

15. **TAXES AND DUTIES:** The Vendor shall be responsible for all taxes including GST, duties, license fees, Insurance, freight charges, local transportation, handling and other incidental charges etc. incurred or accrued until the final delivery of the s/ services or other obligations regarding Services.
17. **FORCE MAJEURE:** The Performance bond shall not be forfeited if the delay in performance is due to a Force Majeure event.
- 17.1 If either party is temporarily rendered unable, wholly or in part by Force Majeure to perform its duties or accept performance by the other party under the Contract it is agreed that on such party, giving notice with full particulars in writing of such Force Majeure to the other party within 07 (Seven) days after the occurrence of the cause relied on, then the duties, of such party as far as they are affected by such Force Majeure shall be suspended during the continuance of any inability so caused but for not longer period and such cause shall as far as possible be removed with all reasonable speed.
- 17.2 If either party is permanently prevented wholly or in part by Force Majeure for period exceeding one (01) month from performing or accepting performance, the party concerned shall have the right to terminate this contract immediately giving notice with full particulars for such Force Majeure in writing to the other party, and in such event, the other party shall be entitled to compensation for an amount to be fixed by negotiations and mutual agreement.
- 17.3 If a Force Majeure situation arises, the Contractor shall promptly notify PTCL in writing of such conditions and the cause thereof. Unless otherwise directed by PTCL in writing, the Contractor shall continue to perform its

obligations under the contract as far as is reasonably practicable, and shall seek all reasonable alter

Native means for performance not prevented by the Force Majeure event.

18 **DOCUMENTATION FOR PAYMENT:** For Payment purpose, the following documents should be sent to SM Central Payments PTCL HQ, G - 8/4 Islamabad, Pakistan:

18.1 Original Contractor's invoice in triplicate showing goods/service description, billing period, quantity, unit price(Pre-GST, GST and Total) and valid for refund of GST duly verified by End User/ PD (Project Director).

18.2 Consignee's Service Acceptance Note (SAN) Certificate / Voucher.

18.2.1 Certificate of satisfactory services duly verified by each floor representative. (*For each monthly payment*)

18.3 Receipt of copy of performance bond duly verified by SM Contracts Turnkey (SW&IT). (In case of first payment only)

18.4 Contractor shall quote prices as per attached BOQ document.

19. SCHEDULE OF PAYMENTS:

19.1 Payments schedule according to P.O will be as under:

- a. 25 % payment after completion of 50 % work done
- b. 50% payment after 75% work done
- c. 25% after completion/ Handing taking over .

FINE/ PENALTY:

20.1 Subject to Clause 17 (Force Majeure), if the Contractor fails to deliver any or all of the Goods or perform the services within the time period (s) specified in the contact, PTCL, shall without prejudice to its other remedies under the contract, have the right to impose penalty.

20.2 A penalty of Rs.1000/day will be imposed if the contractor fails to perform the said work in accordance with the scope of work.

- 20.3 Any fine/ penalty imposed if not paid in cash by Contractor shall be deducted from the running invoice (s) submitted by Contractor. The imposition of penalty upon the Contractor and its payment does not absolve the Contractor from its obligations to delivery or from any other liabilities or obligations under the Contract.
21. Bidder must mention their Vendor Registration code on quotation. In case vendor is not registered, then registration must be done before the issuance of letter of Intent (LOI). Vendor Registration form can be downloaded from PTCL website:
www.ptcl.com.pk/media.
22. All correspondence on the subject may be addressed to the undersigned.
23. Bids shall be submitted in PTCL Headquarters, G-8/4, Islamabad as per instructions provided in tender documents on or before **1200 Hours. Dated: 16-10-2017.**

MANAGER MAINTENANCE

Mubashar Mirza/Manager (Maintenance) HQ/PTCL

Contact office#051-2250127

Email address Mubashar.mirza@ptcl.net.pk

**PAKISTAN
TELECOMMUNICATION
COMPANY LIMITED**

O/O Senior
Manager
Maintenance
PTCL
Headquarters
G-8/4
Islamabad

**Tender #. Mngr/Mtec/Inq/2017-18/
The Senior Manager (Maintenance)
PTCL Headquarters G-8/4,
Islamabad**



Pakistan Telecomm: Company Ltd

**Bill of Quantities for Renoation Works at ICT Hostel CDDT Buidling H-9/1
Islamabad**

SI #	Description	Qty	UNIT	Rate	Amount
1	Removing white or color wash and distemper from plastered / unplastered surface.	430.60	Sqm		
2	Surface preparation (for dampness) by provision of a film with Alkali Resisting primer on plastered wall or ceiling.	430.60	Sqm		
3	P/A Two coats of painting of new or old such as walls including all detached attachment with plastic emulsion paint.	2153.00	Sqm		
	G.Floor (Dining Hall)				
	Celling Sofit	693.00			
	Long walls	660.00			
	Short Wall	420.00			
	Small Wall	30.00			
	Room b/w d/hall & kitchen ceiling sofit	132.75			

	Long walls	295.00			
	Short Wall	180.00			
	Deductons				
	less opening	-114.00			
	less door	-29.75			
	less Al Window	-36.00			
	less Al Window	-60.75			
	Long wall near dining hall	603.25			
	kitchen				
	Celling Soffit	302.50			
	Long walls	110.00			
	Short Wall	137.50			
	Long walls	110.00			
	Short Wall	137.50			
	First Floor				
	Room No.1				
	Celling Soffit	2239.20			
	Celling Soffit between dressing & bath	446.25			
	Long walls	3545.40			
	Short Wall	2422.50			
	Less Al Window	-360.00			
	Less Ennt. Door	-224.78			
	Lesss Toilet door	-162.50			
	wooden almirah	-388.13			
	Attached Bath				
	Celling Soffit	330.63			
	Long walls	431.25			
	Short Wall	431.25			
	Short Wall	380.00			
	Less door	-162.50			
	Less ventilators	-63.40			
	Corridor				
	ceiling soffit	1800.00			
	Long walls	2850.00			
	Short Wall	456.00			
	Staris	67.50			
	Long walls	612.00			
	Roound area near Stairs	73.50			
	stair ceiling landing slab soffit	75.00			
	Mumty Area1	99.75			
	Mumty Area2	135.00			

	Mumty Area3	270.00			
	Mumty Area4	162.00			
	Security Guard Hall at 1st floor ceiling sofit	1140.00			
	Seg-2	106.88			
	Long walls	912.00			
	Short Wall	451.25			
	ceiling sofit Segment Hall-2	698.06			
	Long walls	726.75			
	Short Wall	346.75			
	less windows Hall1	-125.00			
	less door Hall 1	-28.00			
	less door Hall 2	-49.00			
	less door windows Hall 2	-50.00			
	Total Qty FPS	23166.61			
	Qty MKS				
4	One coat of painting on new or old work such as plain and corrugated sheets in roofs, partitions etc (measured flat not girthed) with synthetic enamel paint.	2153.00	Sqm		
5	Spirit polishing to old wood work Complete.	312.00	Sqm		
	Room Doors	656.25			
	Bath doors	510.47			
	Wooden Almirah	1552.50			
	Hall 1 door	70.00			
	Hall 2 door	122.50			
	wooden railing	42.00			
	Door b/w dining & kitchen	133.88			
	store door	105.00			
	kitchen door	105.00			
	Wooden railing at 1st floor	58.10			
	Wooden railing at 1st floor	5.60			
	Total Qty FPS	3361.30			
	Qty MKS				
6	P/a Two coats of synthatic enamel paint on wood work such as doors etc	155.00	Sqm		
	Wooden Almirah shelves	300.00			
	large shelves	1215.00			
	Small side	150.00			
	Total Qty FPS	1665.00			

	Qty MKS				
7	Two coats of synthetic enamel paint on Iron work such as doors etc	67.00	Sqm		
	Mumty iron door	74.75			
	stair railing	67.50			
	Iron duct doors	40.00			
	iron railing	32.06			
	Window Grill	350.00			
	Corridor Grill	157.50			
	Total Qty FPS	721.81			
	Qty MKS				
8	Demolation of un-reinforced lime or cement concrete & premix carpet etc.	6.00	Cum		
	Bath floor	45.00			
	Total Qty FPS	45.00			
	Qty of item # 23-38	154.00			
		199.00			
	Qty MKS				
9	Carefully taking up or down, glazed or encaustic tiling to floors, hearths or walls incl borders, skirting, moldings, capping, etc and CM setting, but not backing.	154.00	Sqm		
	Bath floor	330.63			
	L/Walls	661.25			
	S/Walls	661.25			
	Total Qty FPS	1653.13			
	Qty MKS				
10	Load materials, as in soil / rock on truck / trolley or any other means, carry beyond 10 M (specified in items 01-1 to 01-10) upto 100 M or up 500 M part thereof, unload and stack or spread.	8.00	Cum		
	same qty of item # 23-1				

11	Providing and laying CC Type 'B' as in floor, slabs, surface finished smooth with neat cement and steel trowel, using crushed or broken stone.	2.34	Cum		
	Bath floor	82.66			
	Qty MKS				
12	uPVC vent pipe, 110mm dia, Class complete with plain and solvent cement as specified, supply and fixing.	24.00	Mtr		
		80.00			
	Total Qty FPS	80.00			
	Qty MKS				
13	Supply and fix, 100mm dia, uPVC Elbow/bend, 90°, complete with cement solvent joint and all as specified.	10.00	Each		
14	PPR Pipe with all fittings (i.e sockets, bends, tees, elbows where required) 20mm dia (excl excavation) or fixed to wall, floor (surface or concealed) and ceiling etc, incl caps and plugs supply and fixing.	122.00	Metre		
	For bathrooms	400.00			
	Total Qty FPS	400.00			
	Qty MKS				
15	Supply and fix, POP Tiles (600 mm x 600 mm x 20 mm), fixed in ceiling. partitions and dados etc	156.00	Sqm		
	Room Ceiling soffit	1440.00			
	Ceiling soffit between dressing & bath	233.10			
	Total Qty FPS	1673.10			
	Qty MKS				
16	Supply and fix, POP border, in any shape and design, girth not exc 150 mm, complete.	425.00	Metre		
	Skirting Long walls	373.20			
	Skirting Short Wall	255.00			
	Skirting Corridor L/W	300.00			
	Skirting Corridor S/W	48.00			

	Skirting Ent & store L/W	36.00			
	Skirting Ent & store s/W	34.00			
	Skirting Guard room L/W	96.00			
	Skirting Guard room s/W	47.50			
	Skirting Room B/W D/hall & kitchen L/W	29.50			
	Skirting Room B/W D/hall & kitchen S/W	18.00			
	Hall skiting L/w	66.00			
	Kitchen skiting L/w	42.00			
	Kitchen skiting s/w	27.50			
	Hall skiting s/w	22.00			
	Total Qty FPS	1394.70			
	Qty MKS				
17	Providing and laying Granite tiles glazed/ unglazed in any colour/print/texture exc 1600sqcm but not exc 3700 Sq cm on walls and floor set in neat cement and joints grouted with white/ coloured cement, complete, as specified.	268.00	Sqm		
	Rooms Ground & First Floor				
	Room Flooring	2239.20			
	Filloring between dressing & bath	446.25			
	Skirting Long walls	123.16			
	Skirting Short Wall	84.15			
	Less doors	-12.50			
	Total Qty FPS	2880.26			
18	Cleaning and chemical polishing to terrazzo floor / dado.	445.00	Sqm		
	G.Floor (Dining Hall)				
	Dining Hall Floor	693.00			
	Security Guard Room 1st floor	1140.00			
	Corridor Ground & first floor	1800.00			
	Ent G.Floor & first floor store	612.00			
	Kitchen floor	151.25			
	Room b/w dining hall & kitchen	132.75			
	Skirting Corridor L/W	100.00			
	Skirting Corridor S/W	16.00			
	Skirting Ent & store L/W	12.00			
	Skirting Ent & store s/W	11.33			

	Skirting Guar room L/W	32.00			
	Skirting Guar room s/W	15.83			
	Skirting Room B/W D/hall & kitchen L/W	9.83			
	Skirting Room B/W D/hall & kitchen S/W	6.00			
	Hall skiting L/w	22.00			
	Kitchen skiting L/w	14.00			
	Kitchen skiting s/w	9.17			
	Hall skiting s/w	7.33			
	Total Qty FPS	4784.50			
	Qty MKS				
19	Providing and laying white / light colour/ glazed / non skid tiles exc 400 sq cm, but not exc 900 sq cm area each, on walls and floors, set in neat cement and joints grouted with white /coloured cement, complete, all as specified, Pak made.	64.00	Sqm		
	Floor	330.63			
	Bathroom long wall 1	575.00			
	Bathroom long wall 2	575.00			
	Less door	-100.00			
	Total FPS	1380.63			
	Less 50% QTY	-690.31			
		690.31			
	Total MKS				
20	Providing and laying dark clour/ glazed / non skid tiles exc 400 sq cm, but not exc 900 sq cm area each, on walls and floors, set in neat cement and joints grouted with white /coloured cement, complete, all as specified, Pak made.	64.00	Sqm		
	Add 50% Remaining Qty				
21	Providing & laying Border tiles 100mm wide in any colour/size set in neat cement and joints grouted with white/coloured cement, all as specified pak made.	20.00	Meter		

	Bathroom long wall	38.33			
	Bathroom Short wall	38.33			
	Less door	-13.33			
		63.33			
22	S/F, 25mm thick, white / coloured marble slab around vanity bowel, with brackets etc incl cutting in shape with machine, rubbing, polishing and making the joints water tight, fixed to concrete, brick or stone work.	120.00	Sft		
23	Burnt brick work, in walls 115mm thick, laid and jointed in CM 1:3, straight or to curve with inner radius of 6m and over, upto G.F roof level.	2.00	cum		
24	19mm thick Cement Plaster 1:3, finished as specified	21.00	Sqm		
25	Looking mirror any shape and pattern 5 mm thick (imported).	94.50	Sft		
26	Providing and laying RCC Type 'A', but using crushed or broken stone. as specified in roof slabs,, etc, requiring shuttering. Below venty SlabReinforcement measured and paid separately.	24.00	cft		
27	Supply and fix, bars round, using deformed bars Grade-60 incl cutting, bending, binding and placing reinforcement in position.	55.00	Kg		

28	Providing and laying, 20/22 mm thick Marble tiles (parlenoYellow) for stair riser & treds & Leanding slabes in floors, laid & jointed in white / coloured cement (1:2) incl rubbing, chemical polishing, complete. In all respect as directed by the engineer in charge or as required at site polishing buffing etc complet in all respect.	150.64	Sqm		
29	Tee Stop cock brass, CP, screw down, high pressure, fancy type, 15mm dia, supply and fixing.	30	Each		
30	Supply and fixing, WC apparatus, European pattern, Porta, complete, (coupled set), comprising closet 13 lit flushing cistern, glazed, seat cover, in white/ivory colour, complete, Imported (China), fixed to concrete, brick, stone or wood work, best quality.	10	Each		
31	Double Bib cock, Brass, CP, fancy type, screwed down, BSP, 15 mm dia, supply and fixing.	10	Each		
32	Master Royal bathroom accessories set(101 A) of 6 pieces, consisting of o one towel rod with bracket, one toothbrush holder with glass, and cover, one tissue paper holder, one soap dish, one double hook, one towel ring CP & YC).	10	Each		
33	S/F, Toilet shower, best quality, Pak made, 15 mm dia.	10	Each		
34	Ball valves, brass (Corydon) or other approved pattern, with plastic ball screwed for iron (brass ferrule), 15mm dia, supply and fixing.	30	Each		
35	Supply & fix casted grated CP 100X100 mm	20	Each		
36	Supply & fix Floor trap 100X100 mmdia.	10	Each		

37	Supply and fix, WHB in light colour, glazed ware, 660 mm x 560 mm (IFO pattern or equivalent), one hole ,complete with waste pipe, coupling, chain & plug etc (except mixer), best quality, fixed to concrete, brick, stone, or wood work, Pak made.	12	Each		
38	Basin mixer Economy, cast neck, plastic knob, (356) CP.	12	Each		
39	Wall Shower/Hand Shower type (3202) Royal Series, CP.	10	Each		
40	Sink Mixer (700) victorian CP. Supply & Fixing.	2	Each		
41	Supply and fix, Sink Scullery of Stainless Steel, with Double drainage board, complete, shallow or deep pattern upto 6000 sqcm, super, fixed to concrete, brick, stone or wood work, Pak Made, incl S/F fittings, accessories etc as required.	1	Each		
42	Supply and fix kitchen floor/sink cabinet 600 mm wide and 862 mm high, with First Class Soft wood frame , 19mm thick Teak Veneered board shutter, drawers incl all necessary chromium plated (CP) mongery RCC slab, 25mm thick white/coloured marble slab, PCC inside complete as per IS Arch 17,18 & 19.	4.00	Metre		
	For kitchen	12.42			
	Qty MKS				
43	Supply and fix kitchen Wall Cabinet 381mm wideand 610mm high, 19mm thick Teak Veneered board shutter complete as per IS Arch 17,18 &19, incl all necessary CP mongery fixture and deodar wood edging provided to door cabinets.	6.00	Metre		
	For kitchen	20.00			
	Qty MKS				
44	Gas cooking range, five burner 34" single door complete with thermostat, own, grill, rotisserie and tempered (heat-proof) cystal glass, supply and fixing. NAS Gas	1	Each		

45	Supply & Fix C.P. Locks For cupboard 50 mm complet	30	Each		
46	Supply & Fix C.P. Locks rim or latch 150 mm with bolts and two lever in any shape/pattern, best quality.	20	Each		
47	Supply & fixing Door closer, best quality.	10	Each		
48	Supply and fixing of 5mm thick tinted glass fixed to timber or steel sashes with hard and softwood beads or by the use of rubber lining.	4.00	Sqm		
	at Ground & First floor	13.89			
	at Ground & First floor	27.00			
	at Ground & First floor	6.00			
	Total Qty FPS	46.89			
	Qty MKS				
49	Supply & fix 38 mm thick, 1st Class Soft wood, sashes and doors, gauzed with moulded or chamfered bars, panels filled in with wire gauze 9x9 mesh, 24 gauge excl chowkats, holdfasts and hung with hinges or pivots incl iron mongery as described.	2.00	Sqm		
	servant bath door	16.88			
	Qty MKS				
50	Supply and fix 38 mm thick, Hollow Flush door, Commercial veneered, incl iron mongery all as specified, except chowkats.	2.00	Sqm		
	servant bath door	16.88			
	Qty MKS				
51	Supply of Aluminium Sliding window (Economy Model) of Anodized Aluminium extruded section, exc-1524mm but not exc 3048 mm height as specified, incl fixing on concrete, wood or steel frames complete with all necessary fittings except glass.	1.00	Sqm		
	hostel room	9.00			

52	S/F wrought bow with handle bow 250 mm	30.00	Each		
53	S/F wrought tower bolt 100 mm.	20.00	Each		
	For doors				
	Electrical Works				
54	one fan point, one light point, one bell point, controlled by one switch, wiring complete with PVC single core cable 1.5 mm ² in concealed conduit, stove enamelled, supply and fixing.	40.00	Point		
55	One three pin socket outlet 15 Amps point controlled by one switch, wiring complete with PVC single core cable 2.5 mm ² in concealed conduit, stove enamelled, including earth wire, supply and fixing.	10.00	Point		
56	4 gang switch, 10A, 250V, supply and fixing.	10.00	Point		
57	Ceiling fan supreme Golden Model 48" (1200mm) without regulator, Pak Fans, royal Fans, .	10.00	Each		
58	PHILIPS or equivalent recessed ceiling 18 watt round smd light	10.00	Each		
59	PHILIPS or equivalent recessed ceiling 9 watt round smd light	90.00	Each		
60	Welding charges for Mumty iron door size (5.75x6.5). Complete job.	1	job		
61	Dismanteling of existing wooden doors & re-fixing with proper cutting. Complete in all respect and as per satisfaction of Engineer Incharge.	23.00	job		

62	Taking down Partitions, framing, of any description wall panelling and similar work, incl doors exc 2.60 m super each Hard / Soft wood / aluminum including staking the service ablematerial at site & disposal of rubbish up to any lead & lift partation at first floor hall	1.00	Job		
63	Meter Electric AC 220/250V, single phase, 50 cycle upto 30A, supply and fixing	10.00	each		
64	Gas water heater, complete with burner pilot, thermostat and safety valve, 35 gallons capacity, supply and fixing	3.00	each		
65	Supply & Installation of core 4 " dia uPVC pipe for Air-conditioning system I/C making hole in wall & repairing of walls to match with wxsisting	10.00	Job		
	SUB TOTAL				
	Rebate if any				
	Grand total				

Tender Form #-----

ISSUED TO:

Name and Signature of the Authorized Representative:

Signature of Tender Committee